

RFP 2023-24-004 Multi Purpose Facility at Rodeo Grounds

Questions

- 1) Deadline for Completion of Service / Project has been extended. Please see Addendum #01.

- 2) Site Work- Do the final plans actually reflect location of build, vs the in person site visit with Chuck?

The site work will follow the discussion during the pre-proposal meeting. The Civil was not engineered.

- 3) Provider of data/telephone service.

The data/telephone service will be performed by our IT department.

- 4) In concession area – Is counter finish PLAM with exterior exposure.

The counter will be finish PLAM with exterior exposure.

- 5) Utility pad location? Bollards? Potentially move that location, does not seem conducive to place in fire traffic lane of parking lot.

We will utilize traffic bollards for the utility pads.

- 6) According to discussions with Chuck and Parker & Assoc Addendum #1 – Minisplit is to be installed at concession – Can we get revised Mechanical sheets

Minisplit will replace the unit heater in the concession stand.

- 7) Per Parker & Assoc Addendum #1 – Can we get revised plan sheets M-1, M-5, E-2, E-5, E-6

Architect does not have plan sheets at this time. Please utilize the notes.